




3-Port Non-vented



Load reactive, load control valves with pilot assist combine two valves; a check valve and a relief valve. The check valve allows free flow from the directional valve (port 2) to the load (port 1) while a direct-acting, pilot-assisted relief valve controls flow from port 1 to port 2. Pilot assist at port 3 lowers the effective setting of the relief valve at a rate determined by the pilot ratio.

TECHNICAL DATA NOTE: DATA MAY VARY BY CONFIGURATION. SEE CONFIGURATION SECTION.

Maximum Operating Pressure	5000 psi
Pilot Ratio	3:1
Maximum Recommended Load Pressure	See Technical Features
Adjustment - No. of CCW Turns from Min. to Max. Setting	9
Check Cracking Pressure	25 psi
Factory Pressure Settings Established at	2 in ³ /min.
Maximum Valve Leakage at Reseat	5 drops/min.
Reseat	≥77% of setting
Locknut Hex Size	9/16 in.
Locknut Torque	80 - 90 lbf in.
Seal kit - Cartridge	Buna: 990-202-007
Seal kit - Cartridge	Polyurethane: 990-002-002
Seal kit - Cartridge	Viton: 990-202-006

CONFIGURATION OPTIONS

Model Code Example: MBEALHN

CONTROL (L)

L Standard Screw Adjustment

FUNCTIONAL SETTING RANGE (H)

H 1000 - 4000 psi (70 - 280 bar), 3000 psi (210 bar) Standard Setting

J 2000 - 5000 psi (140 - 350 bar), 3000 psi (210 bar) Standard Setting

SEAL MATERIAL (N)

N Buna-N

V Viton

MATERIAL/COATING

Standard Material/Coating

JAP Stainless Steel, Passivated

/LH Mild Steel, Zinc-Nickel